

prierez	kusy	dĺžka [m]	bežné metre [m]	suma bežné metre [m]	objem [m3]
60mm/ 180mm	24	6.57	157.68	157.68	1.7029
		suma:	klieštiny 60/180		1.70
100mm/ 180m	26	4.71	122.46	122.46	2.2043
		suma:	krokva 100/180		2.20
160mm/ 140mm	2	10.25	20.5	20.5	0.4592
		suma:	pomúrnica 160/140		0.46
160mm/ 160mm	4	1.41	5.64	5.64	0.1444
		suma:	pásik 160/160		0.14
180mm/ 180mm	2	3.17	6.34	6.34	0.2054
		suma:	stípkik 180/180		0.21
100mm/ 140mm	4	1.83	7.32	7.32	0.1025
		suma:	vážnica 100/140		0.1
180mm/ 220mm	1	10.25	10.25	10.25	0.4059
		suma:	vážnica 180/220		0.41
60mm/ 50mm	26	4.71	122.46	122.46	0.3674
		suma:	kontralata 60/50		0.37
plné debnenie			25mm	100m2	2.5
				suma	8.09

1 pomúrnica zložená z 2 kusov

vrcholová vážnica v jednom kuse!!!